

PROJECT SPECIFICATION

Project #:	1919
Project Address:	766 109th Avenue NW, Coon Rapids, MN, 55448
Project Type:	Rehab
Project Manager:	Bjorn Erickson (612.396.8969)
Site Supervisor:	Kelly Vetter (612.271.9116)

SUBCONTRACTED WORK

Approximate Start Date	Type of Work
Ready Now	350-350 Asphalt Paving

SCOPE OF WORK

350-350 ASPHALT PAVING (Subcontractor)

Base:

- 5" thickness of Class 5 recycled concrete. Work to include supply and installation of base.
- Base to be placed up to existing curbs.

Site Work:

- Remove and dispose of existing driveway, approximately 1,200 square feet. Sub cut for driveway, export all excess fill, and verify appropriate compaction. Sub cut expected to be done just prior to driveway installation and will not require an additional trip.

Bituminous:

- The parking and drive entrance shall be constructed of 2.5" inches of bituminous material placed in one lift.
- Size and shape to match existing driveway.

Material Supply:

- All materials supplied by subcontractor.